

Daily Pre-Trip Inspection Checklist - Class A

5. Check manual / automatic air tank drain valves

- Air tank petcocks should be drained daily by pulling color coded lanyards to release any air or moisture. Usually located in front wheel well.
- Lanyards are to be pulled manually and are color coded to identify each tank with a specific system / tank
 - * Silver / clear - Wet Tank
 - * Red - Front (secondary) brake system
 - * Green - Rear (primary) brake system

6. Complete a walk-around of the entire outside of the vehicle and check for the following:

- Fluid Leaks - both on chassis components (e.g. wheels) and on the ground. Note - water dripping during and following A/C use is normal.
- Unusual noises such as air leaks
Proper height of the vehicle to ensure air bags are inflated and vehicle is not leaning
- Any damaged or loose components visible including wiring
- Make sure all compartment bay doors are securely closed and locked
Open and check generator compartment for any damaged or loose components. Close and securely latch generator compartment.
- Check mirrors and windshield wiper blades and arms to be sure that they are secure, not damaged and operate smoothly, Check windshield washers.
- Check electric step to make sure it is retracting completely and free from debris
Check to make sure Hot Water Heater door is latched securely
- Check to make sure that slides are retracted fully and locked (if equipped with locking mechanisms)
- Step back to check up & down sides of coach to roof for any damaged or loose components and that all awnings are fully retracted and locked
- Check underneath coach to make sure jacks are fully retracted and locked in place and for any damaged or loose components
- Check to make sure that power, water and sewer lines are disconnected and securely stowed
If ladder extension is attached to ladder, make sure it is securely fastened

7. Complete an interior check of the vehicle to include the following:

- Check electric and air horn to make sure that they both are in working condition
- Check heater and defroster and test that they both work
- Check to make sure that TV antenna is down and in 'travel' position
- Make sure that all windows are closed and locked
- Check that all counters are clear and all items are securely stowed
- Check to see that all cabinet doors are locked and drawers shut and securely latched (if equipped)
- Check to see that all pocket doors are locked securely with plunger-type floor locks
- Check to make sure that shower door is locked